
**Yothers Road Improvements
S.R. 429 to Plymouth-Sorrento Road**

BID NO.: 2016-13

TO PROSPECTIVE BIDDERS & OTHERS CONCERNED

**THIS ADDENDUM SETS FORTH THE CHANGES AND/OR INFORMATION
AS REFERENCED AND IS HEREBY MADE PART OF AND SHOULD
BE ATTACHED TO THE SUBJECT CONTRACT DOCUMENTS.**

SIGN IN AND INTRODUCTION

PROJECT NAME:

Yothers Road Improvements – work area within 1,100 L.F. stretch - approx.

A) SCOPE OF WORK (Work within approx. 1,100 L.F.)

- I. Survey – silt fence
- II. Grading
- III. Excavation (including asphalt)
- IV. Embankment
- V. Roadway – grading, paving, striping and signage
- VI. Asphalt
- VII. Concrete
- VIII. Sod

B) MISC. INFO.

- A) Plans available - \$25.00 (Non-refundable)
- B) Recommend site visit by all bidders
- C) Contract time is 60 calendar days (from Notice to Proceed Date) to substantial completion and 15 more calendar days to final
- D) Work hours are 7:30 am to 4:30 pm, Monday thru Friday.
- E) Fire hydrant backflow and meter available from City for water. Deposit of \$2,000.00 required. Contractor responsible for water usage.
- F) Contractor shall submit M.O.T. for review and approval by City.

C) BID INFORMATION

- A) Bid opening date July 12, 2016.
- B) Location: City Hall Council Chambers at 10:15 am
- C) Bids must be received in City Clerk's offices no later than 10:00 am the day of bid opening
- D) Engineers estimate \$86,000.00

- E) Qualifications of bidders per section 00020 of specifications
- F) If plans retrieved for Apopka web site.... Check for addendums.
- G) Dispose of excess dirt accordingly. Minimal right-of-way space.
- H) Coordinate work efforts with other contractors on site (traffic light).

After meeting today, all questions shall be submitted in writing and sent to the attention of Ken Gatton via e-mail at kgatton@apopka.net with copy to Rania Nakla at rnakla@apopka.net. No questions will be entertained within 5 business days prior to bid opening.

D) PERMITS

- A) Contractor's responsibility to obtain all necessary permits
- B) No permit required from City of Apopka
- C) Permit required from Orange County (Plymouth-Sorrento Rd.)

E) QUESTIONS

Q. Please clarify the scope as it relates to the removal and replacement of the existing fence on the South side of Yothers Road.

The fence shall be removed by the Contractor and associated costs included with line item for clearing and grubbing. The City will install a new fence at a later date.

Q. Please clarify the scope as it relates to moving the existing fire hydrant.

The City will relocate the existing fire hydrant and will schedule the work prior to the contractor start date.

Q. Please confirm that the two (2) driveway aprons shown on the plans are to be included and that, if necessary, quantity estimates may be adjusted.

The two driveways are included and shall be constructed with 6" thick concrete, 3,000 PSI with wire mesh or fabric. Size shall be as shown on plans.

Q. . No details are shown for the 6" concrete driveway. Section 522 makes mention of it including wire mesh or fiber mesh and it does not state the required psi.

See note above.

F) CLARIFICATIONS:

- 1. The City of Apopka applied for ROW Permit. M.O.T. permit will be the Responsibility of the contractor.***